

Sydney Bathroom Hire

Luxury Sewer Connected Toilet Requirements Check List

There are some important factors that you need to consider before hiring one of our portable toilets.

Please read the following requirements carefully.

- **Suitable access is required.**


Luxury Sewer Connected Toilets are delivered via a Ute and trailer. They are placed on a toilet trolley and wheeled into position. You require a clear access pathway of 1.500m in width, 2.500m in height to wheel the toilet around. You will require 2.600m in clear height if you are to stand the toilet under an awning. Under no circumstances will the driver trolley the toilet up or down stairs (not even one). It is appreciated if the site is clear of obstructions before we arrive to make set up as easy as possible for us, as we do a lot of deliveries per day. Our sewer connect toilets are extremely unique as they have a built in Macerator pump that pumps the human waste directly out of the toilet and into the sewer system on your property. We require access to a single power point, garden tap and a sewer point as illustrated below. We supply the garden hose, power lead and flexible sewer pipe. Our pump can pump up to 50 meters on level ground with 1 meter of head.

- **Electricity** is standard **10 AMP/ 240 volts power supply**. The toilet requires a **single power point**. Please ensure the power points are in good condition. **We supply 30 metre leads that are tagged and tested for your safety**. No power boards or double adaptors can be used. A generator of 5.5 KVA is sufficient for remote locations.
- **Water** needs to be connected so a tap is required. Preferably gardens tap under mains or pump pressure. **We will supply the tap connection and 20 metres of quality hose**. Extra hose can be supplied at your request. **Check to see if your tap leaks when turned on**.
- **Sullage** is discharged through a **32mm flexible hose** pumped automatically into your existing sewer via your overflow relief gully, inspection opening, or similar access point (see picture). **Inspect your outside sewer system for a suitable opening**. If in doubt please contact your local plumber or arrange a pre-hire inspection (costs will apply). Septic tanks and envirocycle type systems are fine. We supply all necessary hoses and connections. **Please advise us if the distance to sewer services is greater than 20 metres. Maximum distance is 50 metres with a one meter rise**.



Sydney Bathroom Hire

- If we cannot install on delivery due to unsuitable access or services you will forfeit your whole hire payment or part there of.
- Ground must be **reasonably level**. If the site is not level please inform us.
- If you **supply labour** to manoeuvre the toilet into position by hand then the **same labour must be provided on pick up or you may be charged extra**.
- A **security deposit** may be required which is refundable once the toilet and its accessories are returned in the same condition as delivered. A condition report will be completed with you on delivery.
- **Toilets must be cleaned out before pick up. Excessive dirt and grime will attract a cleaning fee dependant on time required to return the toilet to the same condition it was in when handed over to you.**
- **Toilets must be left plugged in and turned onto power when we arrive so we can pump out any waste in the toilet or pump itself.**



“For all your portable bathroom solutions”